



D&C Engineers

Concrete plant for Cemex in Chiswick by D&C Engineers



Features included:

- 90m³ per hour concrete batching plant with wet/dry leg
- Two discharge chutes, one offering a half-wet system
- 25-ton below ground receiving hopper
- 22-degree x 600-wide chevron inclined radial conveyor
- Seven compartment 400-ton capacity bins
- 3m³ weigh hopper
- 18-degree x 900-wide flat feed conveyor to mixer and half wet/dry leg
- 3m³ TEKA pan mixer with twin door discharge
- Mixer high pressure washout system
- 3 x 90-ton integral silos
- Cement weigh hopper feeding directly into mixer
- Admix system
- Plant totally enclosed with internal storage areas
- Plant designed to suit split level.

Contact us to discuss plant manufacture and installation today: we look forward to talking to you